BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE

Office of the Executive Engineer Dasarahalli Division,

No.BBMP/EE/DD/Ten/01/2015-16. Date:04.01.2016 Indent No.20442

SCHEDULE-B

NAME OF WORK: Improvements and construction of CC road from Dharmastala Hotel via Cincerut Garden Chaplamma circle to Basavanna temple in Dasarahalli Ward no.15

No.	Description of work	Unit	Qty	Rates Quoted by Contractor M RAJASHEKAR		
				In Figures (Rs.)	In Words (Rs.)	Contr. AMOUNT
1	2	3	4	5	6	7
1	Earthwork excavation for foundation of buildings, water supply, sanitary, lines and electrical conduits either in pits or in trenches 1.5 m and above in width, in hard soil not exceeding 1.5m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead up to 50 m. after breaking of clods complete as per specifications	Cum	70.95	80.0	Rupees Eighty Only	6156.00
2	Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @180 kgs. with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @0.57cum machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	Cum	38.47	4600.0	Rupees Four Thousand Six Hundred Only	176962.00
3	Cement Concrete Pavement :- Construction of un-reinforced, dowel jointed, plain cement concrete pavement over a prepared sub base with 43 grade cement design mix M30 at 360 kg per cum, with 25mm and down size graded granite metal coarse aggregate at 0.69 cum and fine aggregates @ 0.46 cum with superplastizer at 3lts conforming to IS 9103-1999 reaffirmed 2008. coarse and fine aggregate conforming to IS:383, mixed in a batching and mixing plant as per approved mix design, transported to site, laid with a fixed form or slip form paver, spread, compacted and finished in a continuous operation including provision of contraction, expansion, construction and longitudinal joints, joint filler, separation membrane, sealant primer, joint sealant, debonding strip, dowel bar, tie rod, admixtures as approved, curing, compound, finishing to lines and grades as per drawing complete as per specifications.	Cum	178.61	6479.2	Rupees Six Thousand Four Hundred Seventy Nine and Twenty Paise Only	1157249.91

M. Rajashekar

Signature of the Contractor

Executive Engr

4	Providing T.M.T. steel reinforcement for R.C.C. work including straightening, cutting, bending, hooking, placing in position, lapping and /or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design, lines, levels and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications.	Tonne	6.07	68000.0	Rupees Sixty Eight Thousand Only	412760.00
5	Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 4 Km a) Basic rate for haulage of materials as per Item No. 17.4./KSR08 : M100-4.1 Rs. 2.00 Tonne/Km b) Average earth of work 1.28 Tonne/Km Rs. 2.00/Km c) Add loading and unloading (Page 1.36 table)	Cum	76.95	65.0	Rupees Sixty Five Only	5001.75
					Total	17581201.66
					Percentage	-6.39%

Signature of the Contractor

Executive Engineer
Devarahalli Division.